

Customer Information:

July 8, 2025

Charlie West
123 Oak Street
Tucson, Arizona 81234

**Sample
Scope of Work**

Installation

- All work to be done in compliance with Synthetic Turf Council approved installation methods.
- Installers Will Meet Delivery Truck to unload Materials.
- Installer, contractor, or Homeowner, agrees to inspect the roll of pup-grass prior to unloading, if damage is evident they will refuse delivery. They also agree to notify us immediately if any damage is noted. They will have driver make a notation on the BOL, take a picture, and forward it to our office.
- Install approximately 1270 square feet of Pup-Grass® Artificial Grass
- Remove 3" of Soil. Correct Grade if needed to allow for proper drainage
- Place 3" of Recycled Concrete Aggregate or CMB
- Compact to 80% with vibratory compactor.
- Install 1" C-35 (Concrete sand) over base and compact
- Install Pup-Grass® Artificial Grass for Dogs.
- Install Synthetic Grass Edging System supplied by PupGear.
- Seams to be in accordance with Synthetic Turf Council Guidelines
- Pup-Grass to be stretched tight and nail according to Turf Council Guideline
- Install Zeolite infill .25 lbs per sq ft.
- Power broom and hose off dust and debris from all installed Pup-Grass, sidewalks, or patios.
- Contractor will remove left over material i.e. rocks & debris into dumpster and all debris brought on site by contractor.
- Install Zeolite infill .25 lbs per sq ft.
- Power broom and hose off dust,
- Removal of rocks & debris into dumpster and all debris brought on site by contractor.
- Site to be left clean and groomed

Contractor/ Installer, or Homeowner agrees to inspect the roll of all materials prior to unloading, If any damage is evident they will refuse delivery. They also agree to notify us immediately if any damage is noted. They will have driver make a notation on the BOL, take a picture, and forward it to our office.

Owner agrees to keep dogs confined while contractor and crew are on site

Contractor agrees to take video or pictures at the end of the day each day and send to Pup-Grass Project Manager.

Contractor will designate an area away from the home for workers to smoke during breaks.

Contractor agrees that when crew must enter the house they will wear booties or removed footwear, they will also leave bathroom in the same condition as when they enter. I.e. wipe sinks of any dirt.

Contractor agrees that crew will have a designated lunch area. They further agree to clean up their lunch bags drink cups and any additional litter.

Contractor agrees that crew will keep their music at a low volume not to disturb homeowners or neighbors.

Contractor agrees that if the job last over three days, they will install a portable bathroom facility at the contractors expense.

Contractor understands customer has multiple dogs and that when possible all gates will be kept closed except when bringing materials or excavation equipment on to site.